

NORTH BEND ELEMENTARY SCHOOL  
CENTRAL PLANT/FIRE ALARM REPLACEMENT

**ADDENDUM NO. 3**

DATE: February 26, 2020

ENGINEER: Gipe Associates  
1220 East Joppa Road, Suite 223  
Baltimore, Maryland 21286  
Phone: (410) 832-2420

OWNER: Harford County Public Schools

PROJECT: North Bend Elementary School  
1445 N. Bend Rd.  
Jarrettsville, Maryland 21084  
Gipe Project No. 19072

TO: All Prospective Bidders

The following changes are made a part of the Drawings and Specifications for the subject project, dated January 31, 2020. Receipt of this Addendum is to be acknowledged, in the space provided in the Bid Form. Failure to do so may subject the Bid to be considered as non-responsive.

**A. CHANGES TO SPECIFICATIONS**

- ☐ 32 31 13 CHAIN LINK FENCES AND GATES: Paragraph 2.3.A.2.a. Delete and add "a. Line Post: 6-inches in diameter with concrete fill."; Paragraph 2.3.A.2.b Delete and add "b. End, Corner and Pull Post: 6-inches in diameter with concrete fill."

**B. CHANGES TO DRAWINGS**

**1. CIVIL DRAWINGS**

- ☐ None.

**2. ARCHITECTURAL DRAWINGS**

- ☐ None.

**3. MECHANICAL DRAWINGS**

- ☐ None.

**C. RFI QUESTIONS/ANSWERS**

- ☐ You have deleted the bollard detail from the CO.3 drawing, and the bollards that were shown at the underground LP gas tanks. Two bollards are still indicated at the chiller SW corner. Are these bollard still required? **The bollards near the chiller courtyard are indicated as existing on the demolition and new work plans. They remain as is.**

NORTH BEND ELEMENTARY SCHOOL  
CENTRAL PLANT/FIRE ALARM REPLACEMENT

- ❑ The fence detail indicated on A1.0 (addendum #2 drawing) now indicate 6" post at the chiller and LP gas tanks. The new fence specification issued yesterday states line post are 1.9" end, corner post are 2.375". **Refer to this addendum.** If 6" post are required will they be light-industrial-strength, Group IC-L? **As Specified.** No concrete fill? **Refer to this addendum for clarification.**

**D. ATTACHMENTS**

- ❑ None.

**END OF ADDENDUM NO. 3**